

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20979-00-01  
Spot: NWNWSESW Sec/Twnshp/Rge: 12-28S-16W  
1251 feet from S Section Line, 3896 feet from E Section Line  
Lease Name: WELLSFORD TOWNSITE OW Well #: 2  
County: KIOWA Total Vertical Depth: 4750 feet

Operator License No.: 31739  
Op Name: IUKA-CARMI DEVELOPMENT LLC  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4620		WITH 2 SX CMT
PROD	4.5	4737	0	WITH 125 SX CMT
SURF	8.625	468		WITH 360 SX CMT

Well Type: EOR UIC Docket No: E24402.2 Date/Time to Plug: 03/15/2013 9:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: KENNETH GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: SET CIBP @ 4500' WITH 2 SX CMT. RUN TBG TO 1100' & CIRCULATE CMT. PULL TBG & TOP OFF. PRESSURE 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/15/2013 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*CASING SQUEEZED AT 1112' W/200 SX CMT, 3677' W/200 SX CMT, 4150' WITH 50 SX CMT.\*\* SET CIBP @ 4620' WITH 2 SX CMT ON TOP WITH DUMP BAILER. RAN TBG TO 1120'. PUMPED 100 SX CMT CIRCULATING CMT TO SURFACE UP 4 1/2". PULLED TBG OUT & TOPPED OFF 4 1/2" WITH 50 SX CMT. PUMPED 150 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS WITH 150 SX CMT. MAXIMUM PUMP PRESSURE 400 PSIG. SHUT IN PRESSURE 100 PSIG.

Perfs:

Top	Bot	Thru	Comments
4674	4679		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 27 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

MAR 18 2013

KCC DODGE CITY

Signed

Richard W. Lacey  
4/09/13 (TECHNICIAN)