

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07133-00-00
Spot: E2SENV Sec/Twnshp/Rge: 36-14S-14W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MICHEL Well #: 2
County: RUSSELL Total Vertical Depth: 3163 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10	491		150 SX
	L1 5.5	3160		100 sx cement. Liner up to 2920'
PROD	7	2922		100 SX
SURF	10	491		150

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2013 1:00 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: JIM SCHOENBERGER Company: JASON OIL COMPANY, LLC Phone: (785) 483-4204

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls.
03/13/2013- Ordered 200 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2013 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' and pumped 100 sx cement w/300 # hulls.
Pulled tubing to 2000' and pumped 100 sx cement w/300 # hulls.
POOH. Hooked up to casing and pumped 100 sx cement. Circulated muddy water out of braden head.
Ran out of cement. Shut in casing.
03/13/2013- Fluid Down 200'. Hooked to casing and pumped 20 sx cement at 350 psi. Pumped 20 sx cement down Braden head.
GPS: 38.79303 -098.82824

Perfs:

Remarks: QUALITY CEMENTING TICKET # 6582 AND 6583

Plugged through: TBG

RECEIVED
MAR 22 2013

KCC WICHITA

District: 04

Signed R.A.D. KED
4/03/13 (TECHNICIAN)

CM

Form CP-2/3

MAR 19 2013