

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20834-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 16-34S-20W
2980 feet from S Section Line, 2200 feet from E Section Line
Lease Name: SELZER Well #: 16-7
County: COMANCHE Total Vertical Depth: 6500 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6000		
DVT		5442		
PROD	5.5	6191	2815	WITH 450 SX CMT
SURF	8.625	641		WITH 250 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/11/2013 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: PUMP 250# HULLS & 35 SX CMT ON BOTTOM. PLUG AT 830' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 710' WITH 40 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 03/11/2013 2:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMP 250# HULLS & 35 SX CMT ON BOTTOM. 1ST PLUG AT 830' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 710' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6031	6100		
5075	5175		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
3/11/13 (TECHNICIAN)

RECEIVED
MAR 22 2013
KCC DODGE CITY