

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20942-00-00
Spot: S2SEW Sec/Twnshp/Rge: 4-32S-39W
2970 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SULLIVAN A Well #: 1
County: MORTON Total Vertical Depth: 6000 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	51		WITH 24 SX CMT
DVT		3180		WITH 700 SX CMT
PROD	5.5	6000	0	WITH 1325 SX CMT
SURF	8.625	1725		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2013 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CHECK FLUID LEVEL. CIBP WITH 2 SXC MT OR 25 SX CMT WITH 100# HULLS. RUN SPACER. PLUG AT DV TOOL WITH 15 SX CMT. SPACER TO 1800'. PLUG AT 1800' WITH 30 SX CMT. PLUG AT 600' - 0' WITH 70 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 02/08/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 100# HULLS TO 5548'. SPACER TO 3200'. TAG WITH SLICK LINE FLOAT. PLUG AT 3200' WITH 15 SX CMT. SPACER TO 1800'. TAG WITH SLICK LINE FLOAT. PLUG AT 1800' WITH 30 SX CMT. SPACER TO 600'. TAG WITH SLICK LINE FLOAT. PLUG AT 600' TO 0' WITH 70 SX CMT. PRESSURE TO 500#. HOLDING. PUMP 15 SX CMT DOWN ANNULUS. PRESSURE TO 500#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
5544	5548		
5522	5527		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
FEB 18 2013
KCC DODGE CITY

Signed

Ken Jehlik
2/13/13

(TECHNICIAN)

RECEIVED
FEB 28 2013
KCC WICHITA

Form CP-2/3

AGW