

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25534-00-00  
Spot: NENENWSE Sec/Twnshp/Rge: 1-18S-26W  
2550 feet from S Section Line, 1498 feet from E Section Line  
Lease Name: KU-DINGES Well #: 1  
County: NESS Total Vertical Depth: 4579 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	216		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/13/2013 11:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 02/14/2013 1:15 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed \_\_\_\_\_  
3/13/13

(TECHNICIAN)

RECEIVED

FEB 15 2013

KCC DODGE CITY

RECEIVED

FEB 22 2013

KCC WICHITA

Form CP-2/3

AM