

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00227-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 14-22S-35W  
1320 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: HAVEL UNIT Well #: 1  
County: KEARNY Total Vertical Depth: 2710 feet

Operator License No.: 32606

Op Name: DEVON ENERGY PRODUCTION COMPANY  
Address: 333 W SHERIDAN AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1000		
CIBP		2100		WITH 4 SX CMT
PROD 7		2537	0	WITH 100 SX CMT
SURF	10.75	196		WITH 150 SX CMT

*[Handwritten signature]*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/20/2013 12:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KURT HIRSCHLER Company: DEVON ENERGY Phone: (806) 255-0449

Proposed Plugging Method: CIBP @ 2500' WITH 3 SX CMT. CIBP @ 1000'. TEST CASING. PERFORATE AT 950'. ESTABLISH INJECTION. PUMP 100 SX CMT OVER CASING VOLUME OR CIRCULATE. PERFORATE @ 450'. CIRCULATE TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/20/2013 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

5 1/2" SLOTTED LINER 2563' TO 2710'. CIBP @ 2100' WITH 4 SX CMT. CIBP @ 1000'. TEST CASING TO 700#. HOLDING. PERFORATE AT 950'. BREAK DOWN AT 700#. INJECTION RATE 2 BPM @ 500#. PUMP 100 SX 60/40 POZMIX 4% GEL TO SPOT LEAVING 40 SX CMT OUTSIDE 7" CASING & 60 SX CMT INSIDE 7" CASING AT 500 PSI INCREASING TO 750 PSI. PERFORATE @ 450'. CIRCULATE CMT TO SURFACE USING 150 SX 60/40 POZMIX 4% GEL & 70 SX CLASS A CMT LEAVING 7" CASING & 7" X 10 3/4" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2563	2710		

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A CMT BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
FEB 28 2013  
KCC DODGE CITY

Signed

*[Handwritten signature: Ken Jehlik]*  
3/5/13  
(TECHNICIAN)

RECEIVED  
MAR 05 2013  
KCC WICHITA

Form CP-2/3

*[Handwritten initials]*