

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26448-00-00
Spot: W2W2NE Sec/Twnshp/Rge: 5-12S-17W
1320 feet from N Section Line, 2310 feet from E Section Line
Lease Name: SHUTTS Well #: 10
County: ELLIS Total Vertical Depth: 3723 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1340		500 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/13/2013 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KELLY BRANUM Company: DUKE DRILLING CO., INC. Phone: (785) 324-1414

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 04/13/2013 1:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3597 w/50 sx
2nd plug @1390 w/50 sx
3rd plug @750 w/80 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

APR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed *Marvin Mills*
4/13/13 (TECHNICIAN)

CM

APR 22 2013