

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20849-00-03
Spot: SENWNWSE Sec/Twnshp/Rge: 22-33S-32W
2000 feet from S Section Line, 2161 feet from E Section Line
Lease Name: ARKALON Well #: 2-22
County: SEWARD Total Vertical Depth: 3101 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2420		WITH 2 SX CMT
CIBP		2830		WITH 2 SX CMT
PROD	5.5	3101	1965	WITH 180 SX CMT
SURF	8.625	1422		WITH 600 SX CMT

Well Type: SWD UIC Docket No: D27466.0 Date/Time to Plug: 02/08/2013 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2820' & 2 SX CMT. CIBP @ 2420' & 2 SX CMT. PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 02/08/2013 1:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 2830' WITH 2 SX CMT. CIBP @ 2420' WITH 2 SX CMT. SPOTTED PLUGS THROUGH TBG. 1ST PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2876	3046		
2520	2536		
2488	2500		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

FEB 11 2013

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

*cc to UIC 2/28/13
3/13/13*

RECEIVED

FEB 22 2013

KCC WICHITA

Form CP-2/3

Handwritten signature