

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21539-00-01
Spot: SENWNWNW Sec/Twnshp/Rge: 28-30S-17W
4848 feet from S Section Line, 4751 feet from E Section Line
Lease Name: BOOTH Well #: 1-28
County: KIOWA Total Vertical Depth: 5720 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4900		
PROD	5.5	5527	1340	WITH 150 SX CMT
SURF	8.625	784		WITH 335 SX CMT

Well Type: PI UIC Docket No: D28999.0 Date/Time to Plug: 02/18/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4900'. RUN TBG TO 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 820' WITH 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2013 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4900' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1092' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 815' WITH 100# HULLS MIXED IN WITH 14 SX GEL & 50 SX CMT. 3RD PLUG AT 406' WITH 40 SX CMT. 4TH PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5527	5720		
4957	4980		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
3/17/13 (TECHNICIAN)

RECEIVED
FEB 28 2013
KCC DODGE CITY

RECEIVED
MAR 05 2013
KCC WICHITA

Form CP-2/3

Handwritten initials