

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21385-00-00
Spot: S2N2NESE Sec/Twnshp/Rge: 33-29S-19W
2247 feet from S Section Line, 643 feet from E Section Line
Lease Name: NORMA K Well #: 1
County: KIOWA Total Vertical Depth: 5250 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4900		WITH 2 SX CMT
CIBP		5054		
PROD	5.5	5232	2387	WITH 235 SX CMT
SURF	8.625	562		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4900' & 2 SX CMT. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 590' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2013 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4900' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1324' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 599' WITH 100# HULLS IN 7 SX GEL & 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4952	4958		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 14 2013
KCC DODGE CITY

Signed

Stephen Pfeifer
2/13/13
(TECHNICIAN)

RECEIVED
FEB 22 2013
KCC WICHITA