

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20648-00-00
Spot: SESW Sec/Twnshp/Rge: 8-29S-39W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: POWELL Well #: 1-8
County: STANTON Total Vertical Depth: 5612 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1850		
CIBP		5400		
PROD	4.5	5612	0	WITH 425 SX CMT
SURF	8.625	1813		WITH 770 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/11/2013 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING REPORT SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5400' WITH 2 SX CMT. CIBP @ 1850'. TEST CASING TO 700#. HOLDING. PERFORATE AT 1840'. INJECTION RATE 1 1/2 BPM @ 800 PSI. PUMP 25 SX CMT, 50# HULLS THEN 25 SX CMT TO SPOT THROUGH PERFS AT 1840' AT 600# DECREASING TO 400#. WITH HULLS AT PERFS, PRESSURED TO 800 SPI. LEFT 25 SX CMT IN THE 4 1/2" X 8 5/8" ANNULUS & 25 SX CMT *INSIDE* THE 4 1/2" CASING. PERFORATE AT 600'. CIRCULATE CMT TO SURFACE WITH 160 SX CMT, LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5522	5529		

RECEIVED
MAR 20 2013
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

RECEIVED
MAR 14 2013
KCC DODGE CITY

Signed *[Signature]* (TECHNICIAN)