

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21166-00-00
Spot: E2SWSNW Sec/Twnshp/Rge: 1-2S-30W
2310 feet from N Section Line, 1787 feet from W Section Line
Lease Name: ANDERSON FARMS Well #: 1-1
County: DECATUR Total Vertical Depth: 4060 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 10390 BRADFORD RD. SUITE 201
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	258		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/02/2013 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGIE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 03/02/2013 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @2549 w/25 sx
2nd plug @1860 w/100 sx
3rd plug @308 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

RECEIVED
MAR 13 2013

KCC WICHITA

District: 04

Signed _____

[Signature]
3/20/13 (TECHNICIAN)

MAR 05 2013