

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-21823-00-01  
Spot: SWSWSWSW Sec/Twnshp/Rge: 26-31S-10E  
149 feet from S Section Line, 5123 feet from E Section Line  
Lease Name: JONTRA Well #: 5  
County: ELK Total Vertical Depth: 2110 feet

Operator License No.: 34468  
Op Name: CONNER, RICK  
Address: 502 E. 6TH AVE PO BOX 494  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1970		PACKER TYPE AND SETTING DEPTH: J PACKER @ 1970
PROD	4.5	3596		
SURF	7	40		
T1	2.375	1970		

Well Type: EOR UIC Docket No: E20965.3 Date/Time to Plug: 03/08/2013 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50' plug at 1000' and 550' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report: Ran 1" to 2080' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 70 sacks of cement were used to plug this well.

Perfs: \_\_\_\_\_  
  
RECEIVED  
MAR 12 2013  
KCC Chanute Dist. #3  
  
DS  
  
RECEIVED  
MAR 15 2013  
  
KCC WICHITA

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.  
Plugged through: TBG

District: 03

Signed [Signature]  
3/20/13 (TECHNICIAN)  
\*cc to MIT 3/20/13