

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21143-00-00
Spot: SWSE Sec/Twnshp/Rge: 8-25S-9E
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HENDRICKSON A Well #: 2
County: GREENWOOD Total Vertical Depth: 2335 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2334		60 SX
SURF	7	37		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2012 12:00 AM
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC
Proposal Revd. from: MATT OSBORN Company: _____ Phone: (620) 583-5527

Proposed Plugging Method: Remove fluid and liner, backfill immediately

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2012 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 2261' pumped 20 sxs cement, shot casing @ 900' & 150' pulled tubing to 900'
pumped 20 sxs cement, pulled tubing to 150' pumped 47 sxs cement to surface, gel spacers
between cement plugs.

RECEIVED

MAR 11 2013

KCC Chanute Dist. #3

MH

RECEIVED

MAR 13 2013

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Mik [Signature]
3/21/13 (TECHNICIAN)