

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22944-00-00  
Spot: SENENE Sec/Twnshp/Rge: 34-33S-13W  
990 feet from N Section Line, 330 feet from E Section Line  
Lease Name: SPRIGGS Well #: 1-34  
County: BARBER Total Vertical Depth: 5230 feet

Operator License No.: 33638  
Op Name: METRO ENERGY GROUP, INC.  
Address: 1500 N. MARKET ST., STE B-106  
SHREVEPORT, LA 71107

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4600		
CIBP		4850		
PROD	4.5	5223	2550	WITH 290 SX CMT
SURF	8.625	241		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2013 12:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND TO 4397' WITH 4 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 01/07/2013 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SAND TO 4400' & 4 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 269' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5025	5030		VIOLA
5020	5023		VIOLA
5014	5017		VIOLA
5003	5008		VIOLA
4674	4682		MISSISSIPPI
4660	4668		MISSISSIPPI
4447	4450		SWOPE

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

JAN 11 2013

KCC DODGE CITY

RECEIVED  
JAN 14 2013

KCC WICHITA

19 007