

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20198-00-00  
Spot: E2W2SWSW Sec/Twnshp/Rge: 29-16S-36W  
660 feet from S Section Line, 540 feet from W Section Line  
Lease Name: LADDER CREEK Well #: 29-1  
County: WICHITA Total Vertical Depth: 5020 feet

Operator License No.: 31783  
Op Name: MID-CONTINENT ENERGY OPERATING  
Address: 100 W 5TH ST STE 450  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	437		WITH 270 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2012 5:00 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: LARRY HINDERLITER Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2530' WITH 50 SX CMT. 2ND PLUG AT 1520' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 12/18/2012 7:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2530' WITH 50 SX CMT. 2ND PLUG AT 1520' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
JAN 14 2013  
KCC WICHITA

District: 01

Signed Michael Maier  
2/19/13 (TECHNICIAN)

RECEIVED  
DEC 31 2012  
KCC DODGE CITY

*Handwritten mark*