

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25524-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 15-17S-23W
2235 feet from S Section Line, 335 feet from W Section Line
Lease Name: SARGENT Well #: 1-15
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/17/2013 8:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1770' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 01/17/2013 10:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1770' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

RECEIVED
JAN 31 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed [Signature]
2/10/13 (TECHNICIAN)

RECEIVED

JAN 24 2013

KCC DODGE CITY

[Handwritten mark]