

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20394-01-00  
Spot: SESESE Sec/Twnshp/Rge: 5-26S-29W  
245 feet from S Section Line, 529 feet from E Section Line  
Lease Name: MILLER Well #: 8-1H  
County: GRAY Total Vertical Depth: 5226 feet

Operator License No.: 34729  
Op Name: SANCHEZ OIL & GAS CORPORATION  
Address: 1111 BAGBY, STE 1800  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	80		
II	7	4871	0	WITH 350 SX CMT
PROD	4.5	9800		WITH 480 SX CMT
SURF	9.625	1515		WITH 600 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2013 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: PHIL CURRY Company: SANCHEZ OIL & GAS Phone: (713) 783-8000

Proposed Plugging Method: PLUG OFF ABANDONED HORIZONTAL LET BEFORE KICKING OFF ON NEW ONE. COMPANY PLUGGED WELL BEFORE NOTIFYING KCC.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 02/09/2013 6:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

2/5/13: SET WHIPSTOCK FROM 4631'-4669'. SET RETAINER AT 4673'. PUMPED 300 SX CMT & LOST RETURNS AT 4645'. 2/9/13: SET ANOTHER RETAINER AT 4546'. PUMPED 300 SX CMT & CMT HELD. DRILLED OUT CEMENT TO WHIPSTOCK & KICKED OFF ON HORIZONTAL LEG.

RECEIVED  
KANSAS CORPORATION COMMISSION  
**MAR 27 2013**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED. \*\*COMPANY IS BEING INVOICED FOR THE INTERVAL BETWEEN 4546' TO 9772'.\*\*

Plugged through: DP

District: 01

RECEIVED

MAR 19 2013

KCC DODGE CITY

Signed

Richard W. Lacey  
03/13 (TECHNICIAN)