

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23925-00-00  
Spot: NWNEENW Sec/Twnshp/Rge: 17-28S-4E  
15 feet from N Section Line, 2100 feet from W Section Line  
Lease Name: PROHASKA Well #: 1  
County: BUTLER Total Vertical Depth: 2504 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1640		
CIBP		1800		
CIBP	5.5	2290		
CIBP		2400		
PROD	5.5	2502	746	100 SX
SURF	8.625	215		115 SX
T1	2.875	1794		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/13/2013 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2534

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 02/13/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1640', DUMP BAILED 4 SXS CEMENTON TOP OF CIBP. CUT CASING @ 746', LAYED DOWN 25 JOINTS OF 5-1/2" CASING. RIH W/WORKSTRING @ 262', COPELAND ACID SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 130 SXS 60/40 4% GEL TO SURFACE. CEMENT CIRCULATED. COPELAND CEMENT TICKET #38240.

Perfs:

Top	Bot	Thru	Comments
2450	2453	CSG	
2294	2297	CSG	
2261	2271	CSG	
1758	1762	CSG	
1666	1672	CSG	

RECEIVED  
MAR 19 2013

Remarks: THIRD CIBP SET @ 2400'

KCC WICHITA

Plugged through: TBG

District: 02

Signed Duane Krueger  
2/27/13 (TECHNICIAN)  
14