

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01724-00-00
Spot: NESWSE Sec/Twnshp/Rge: 18-9S-20W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: TOWNS Well #: 3
County: ROOKS Total Vertical Depth: 3803 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 277
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3.5	3788		250 sx
PROD	5.5	3789		350 SX
SURF	8.625	298		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2013 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM CORP Phone: (620) 564-3002

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2013 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3445' and pumped 50 sx cement.
Pulled tubing to 2144' and pumped 75 sx cement.
Pulled tubing to 1076' and pumped 85 sx cement to circulate to surface.
Pulled all tubing and topped off 3 1/2" liner w/90 sx cement w/100 # hulls. While topping off 3 1/2" liner well went on slight vacuum.
02/04/2013-Topped off 3 1/2" liner w/35 sx cement.

GPS: 39.26672 -099.59293

Remarks: QUALITY WELL SERVICE TICKET # 5822

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

FEB 19 2013

Form CP-2/3

KCC WICHITA

FEB 18 2013