

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21141-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 16-1S-27W
400 feet from N Section Line, 890 feet from W Section Line
Lease Name: HANCHERA Well #: 1-16
County: DECATUR Total Vertical Depth: 3634 feet

Operator License No.: 33629
Op Name: GREAT PLAINS ENERGY, INC.
Address: 6121 S 58TH ST, STE B
LIN COLN, NE 68516

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3634		160 SX
SURF	8.75	260		185 SX
T1	2.375	3600		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2013 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: HAROLD BELLERIVE Company: GREAT PLAINS ENERGY INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 5 sx gel and 300 # hulls.
8 5/8" surface casing set at 260' w/185 sx cement. 4 1/2" production casing set at 3634' w/160 sx cement.
TD 3634', PBTD 3586'. Perforations: 3353'-3357, 3386'-3389, 3312'-3314' and 3270'-3276'.
Stage Collar set at 1979' was not cemented.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2013 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2000', 1400' and 255'.
Ran tubing to 3200' and pumped 5 sx gel followed by 50 sx cement w/200 # hulls.
Pulled tubing to 2000' and pumped 125 sx cement w/100 # hulls.
Pulled tubing to 700' and pumped 250 sx cement. Cement to surface from 8 5/8" surface casing and 4 1/2" production casing. Pulled tubing to surface. Topped with 25 sx cement. Casing full of cement.

GPS: 39.97199 N -100.36250 W

Perfs:

Top	Bot	Thru	Comments
3386	3389		
3353	3357		
3312	3314		
3270	3276		

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENT COMPANY LLC TICKET # 702

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

✓ 5/13/13

CM

APR 18 2013