

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19524-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 17-24S-13E
2020 feet from S Section Line, 2199 feet from E Section Line
Lease Name: EAST ERICKSON Well #: 2
County: GREENWOOD Total Vertical Depth: 1621 feet

Operator License No.: 33913
Op Name: WINTERSCHIED OIL, LLC
Address: 764 RD 70
OLPE, KS 66865

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/08/2013 8:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' CEMENT PLUG @ 1560' 50' CEMENT PLUG @ 540' 210' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/18/2013 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:
SET BOTTOM BRIDGE @ 1560' INSIDE OF 7" CASING, DUMPED 5 GAL. OF LARGE ROCK & 6 GAL. OF CHAT MIXED & DUMPED 8 SXS CEMENT W/DUMP BALER, RAN 2" TUBING TO 540' PUMPED 25 SXS CEMENT, PULLED TUBING TO 210' PUMPED 25 SXS CEMENT TO SURFACE, PULLED TUBING OUT RAN TUBING TO OUTSIDE OF 7" TO 137' PUMPED 180 SXS CEMENT TO SURFACE.

Perfs:
RECEIVED
FEB 04 2013
KCC Chanute Dist. #3
MH
RECEIVED
FEB 06 2013
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03

Signed *Michael Heffern*
3/26/13 (TECHNICIAN)