

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21186-00-00
Spot: NENENWNE Sec/Twnshp/Rge: 14-24S-17W
324 feet from N Section Line, 1618 feet from E Section Line
Lease Name: MALM Well #: 4-14
County: EDWARDS Total Vertical Depth: 4481 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4440		
PROD	4.5	4471	2215	WITH 225 SX CMT
SURF	8.625	265		WITH 210 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2013 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4250' WITH 4 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2013 3:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4236' WITH 4 SX CMT ON TOP OF DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4300	4325		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

APR 16 2013

KCC DODGE CITY