

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21568-00-00
Spot: NENENW Sec/Twnshp/Rge: 15-25S-17W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: WHEATON TRUSTS 'B' Well #: 1-15
County: EDWARDS Total Vertical Depth: 4700 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4704	2245	WITH 150 SX CMT
SURF	8.625	730		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2013 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4450' WITH 4 SX CMT. PLUG AT 1210' WITH 15 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 04/11/2013 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4436' WITH 4 SX CMT. 1ST PLUG AT 1210' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 760' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4518	4518		
4511			
4507	4509		
4503	4505		
4502	4511		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Richard G. Lacey
4/25/13

(TECHNICIAN)

RECEIVED

APR 15 2013

KCC DODGE CITY

Form CP-2/3