

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20205-00-00  
Spot: S2N2SEW Sec/Twnshp/Rge: 12-32S-32W  
1846 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: LLOYD Well #: 1-12  
County: SEWARD Total Vertical Depth: 6052 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5782		
PROD	4.5	5816	1696	WITH 180 SX CMT
SURF	8.625	1665		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2013 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT & 150# HULLS TO 5300'. PLUG AT 1690' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT. MUD SPACER BETWEEN PLUGS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 05/02/2013 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 150# HULLS & 25 SX CMT. DISPLACED TO 5300'. PRESSURED UP. LOAD HOLE WITH MUD. 1ST PLUG AT 1685' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5463	5471		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

Richard M. Lacey  
5/10/13 (TECHNICIAN)

RECEIVED

MAY - 3 2013

KCC DODGE CITY

Form CP-2/3

*Handwritten signature*