

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20610-00-00
Spot: SWNENW Sec/Twnshp/Rge: 23-14S-15W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: FURTHMEYER Well #: 7
County: RUSSELL Total Vertical Depth: 3215 feet

Operator License No.: 33830
Op Name: HEWITT ENERGY GROUP, INC.
Address: 15 W S TEMPLE STE 1050
SALT LAKE CITY, UT 84101

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 5.5 | 3215 | | 100 SX |
| SURF | 8.62 | 216 | | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2013 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 786-1031

Proposed 02/11/2013 - Ordered 300 sx 60/40 pozmix no gel.
Plugging 02/12/2013 - Ordered 300 sx 60/40 pozmix no gel.
Method: Worked on well for about 1 1/2 weeks. Started to lose ground on cleaning out to bottom. Made it to bottom at one time, moved off and when they got back could only get to 600', then to 502'. Worked with different mills and bits and circulated mud out of well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2013 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

02/11/2013 - Got tubing to only 502'. Out side of casing and hanging up.
Pulled tubing to 495' pumped 175 sx cement through bit with a little show of cement.
POOH. Hooked to casing and pumped 125 sx cement and a little show of cement.
Circulated to the cellar. Little show = watered down cement or cement water.
02/12/2013 - Ran tubing in and tagged at 196'. Hooked to tubing and pumped 25 sx cement.
Cement circulated to pit.
POOH. Hooked to casing and pumped 10 sx cement at 300 psi. Started to circulate in cellar.
Shut down and shut in casing. Put some cement in cellar and checked in the morning.
02/13/2013 - Casing full and cellar full.

GPS: 38.82392 -098.96101

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3203 | 3206 | | |

Remarks: COPELAND CEMENTING AND ACID TICKET # 38300 AND 38294

Plugged through: TBG

District: 04

Signed

Ray Dinkel
3/08/13

(TECHNICIAN) RECEIVED

MAR 06 2013 Form CP-2/3

KCC WICHITA

FEB 27 2013