

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20730-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 23-14S-15W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: NEIDENTHAL Well #: 9
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 33830
Op Name: HEWITT ENERGY GROUP, INC.
Address: 15 W S TEMPLE STE 1050
SALT LAKE CITY, UT 84101

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3279		100 SX
SURF	8.265	283		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2013 2:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 786-1031

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement.
Worked on this well for 2 1/2 weeks off and on and got to 898'. Had hard bottom and could not make any more hole.
Leaving 14 joints of 2 7/8" tubing in well.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2013 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing with difficulty to 898'. Pulled tubing up to 870' and pumped 220 sx cement.
Cement circulated to pit.
POOH and hooked on to casing and pumped 25 sx cement at 350 psi. Shut in pressure 350 psi.
Hooked to braden head and pumped 5 sx cement at 250 psi. Shut in pressure 250 psi.

GPS: 38.82458 -098.95321

Perfs:

Top	Bot	Thru	Comments
3244	3246		

Remarks: COPELAND CEMENT AND ACID TICKET # 38282

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
3/08/13 (TECHNICIAN)

FEB 11 2013

RECEIVED
FEB 14 2013 Form CP-2/3
KCC WICHITA