

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20888-00-01  
Spot: NENENE Sec/Twnshp/Rge: 16-34S-20W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SELZER Well #: 16-5  
County: COMANCHE Total Vertical Depth: 6500 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6020		
CIBP		6102		
COND	20	41		
DVT		5700		
PROD	5.5	6249	4425	WITH 225 SX CMT
SURF	8.625	698		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2013 4:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: TBG FISH AT 4808' WITH 30 SX CMT ON BOTTOM. PLUG AT 830' WITH 15 SX GEL & 40 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 02/14/2013 6:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 6102' & 6020'. TBG FISH @ 4808', 30 SX CMT ON BOTTOM. 1ST PLUG AT 830' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 36' WITH 15 SX CMT. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6104	6108		
6076	6094		
5103	5272		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

FEB 19 2013

KCC DODGE CITY

Signed

*Richard W. Long*  
2/18/13

(TECHNICIAN)

RECEIVED

FEB 22 2013

KCC WICHITA

Form CP-2/3