

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22421-00-00

Spot: NENESENE

Sec/Twnshp/Rge: 27-18S-29W

1485 feet from N Section Line,

1 feet from E Section Line

Lease Name: WR UNIT

Well #: 1-27

County: LANE

Total Vertical Depth: 4645 feet

Operator License No.: 3842

Op Name: LARSON ENGINEERING, INC. DBA LAR

Address: 562 W STATE RD 4

OLMITZ, KS 67564

String Size Depth (ft) Pulled (ft) Comment

SURF 8.625 281

WITH 175 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/16/2013 2:30 PM

Plug Co. License No.: 33935

Plug Co. Name: H. D. DRILLING, LLC

Proposal Rcvd. from: LOU TRESNER

Company: H. D. DRILLING, LLC

Phone: (785) 372-5419

Proposed Plugging Method: 1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 310' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: NONE

Date/Time Plugging Completed: 02/16/2013 4:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 310' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

RECEIVED

FEB 28 2013

KCC DODGE CITY

Signed

Stephen J Pfeifer
3/06/13
(TECHNICIAN)

RECEIVED

MAR 05 2013

KCC WICHITA

Form CP-2/3

RAW