

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-30214-00-01
Spot: SESWSE Sec/Twnshp/Rge: 18-9S-20W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: JOHN TOWNS Well #: 6
County: ROOKS Total Vertical Depth: 3794 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 277
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3752		
PROD	5.5	3791		175 SX
SURF	8.625	293		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2013 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM CORP. Phone: (620) 564-3002

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2013 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3451' and pumped 150 sx cement w/200 # hulls.
Pulled tubing to 2311' and pumped 200 sx cement w/200 # hulls to circulate cement to surface.
Pulled all tubing and topped off 5 1/2" casing w/35 sx cement

GPS: 39.26486 -099.59278

Perfs:

Top	Bot	Thru	Comments
3430	3436		

Remarks: QUALITY WELL SERVICE TICKET # 5809

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)
2/28/13

CM

RECEIVED
FEB 19 2013

Form CP-2/3

FEB 18 2013

KCC WICHITA