

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01723-00-00
Spot: SWSESE Sec/Twnshp/Rge: 18-9S-20W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: TOWNS Well #: 2
County: ROOKS Total Vertical Depth: 3783 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 277
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3760		175 sx
PROD	5.5	3779		300 SX
SURF	8.625	275		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2013 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM CORP Phone: (620) 564-3002

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2013 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3451' and pumped 125 sx 60/40 pozmix 4% gel cement with 200 # hulls.
Pulled tubing to 2023' and pumped 125 sx 60/40 pozmix 4% gel cement w/200 # hulls to circulate cement to surface.
Pulled all tubing. Topped off 4 1/2" liner w/45 sx 60/40 pozmix 4% gel cement.

GPS: 39.26482N -099.59051W

Remarks: QUALITY WELL SERVICE TICKET # 5823

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

✓ 2/28/13

FEB 13 2013

RECEIVED
FEB 19 2013

Form CP-2/3

KCC WICHITA