

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-30195-00-00
Spot: E2W2NWNW Sec/Twnshp/Rge: 28-4S-18W
4620 feet from S Section Line, 4785 feet from E Section Line
Lease Name: BREDEMEIR Well #: 1
County: PHILLIPS Total Vertical Depth: 3290 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3227		250 SX
SURF	8.625	216		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2013 3:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix 4% gel cement, 2% common cement and 200 # hulls. Rods, pump and tubing stuck in hole at 1000'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2013 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1000' and pumped 120 sx 60/40 pozmix 4% gel 2% cc to circulate to surface.
Pulled tubing and pumped 15 sx 60/40 pozmix 4% gel 2% cc to top off 5 1/2" casing.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 55 sx 60/40p pozmix 4% gel 2% cc. Pressured to 300 psi.

GPS: 39.68158 N -099.36378 W

Perfs:

Top	Bot	Thru	Comments
3225	3228		
3206	3209		
3188	3191		
3150	3153		
3112	3115		
3051	3054		

Remarks: ALLIED TICKET # 54169

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 05 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Pat Bedore
4/10/13 (TECHNICIAN)

CM