

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21443-00-00
Spot: NWNEENENW Sec/Twnshp/Rge: 9-25S-17W
4962 feet from S Section Line, 2969 feet from E Section Line
Lease Name: BRITTON Well #: A 1
County: EDWARDS Total Vertical Depth: 4535 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3700		WITH 2 SX CMT
PROD	4.5	4534	2180	WITH 150 SX CMT
SURF	8.625	277		WITH 190 SX CMT

Well Type: SWD UIC Docket No: D28246.0 Date/Time to Plug: 04/01/2013 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SET CIBP @ 3700' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 04/01/2013 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 3700' WITH 2 SX CMT ON TOP WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3740	3744		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik
(TECHNICIAN)
cc to MIC 4/16/13

RECEIVED

APR - 5 2013

KCC DODGE CITY

Form CP-2/3

AND