

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21458-00-01
Spot: W2W2W2 Sec/Twnshp/Rge: 9-25S-17W
2633 feet from S Section Line, 356 feet from W Section Line
Lease Name: BRITTON A Well #: 2
County: EDWARDS Total Vertical Depth: 4542 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2170		WITH 2 SX CMT
CIBP		2320		
DVT		2742		WITH 160 SX CMT
PROD	4.5	4535	1221	WITH 125 SX CMT
SURF	8.625	288		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/02/2013 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SET CIBP @ 2170' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2013 4:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2170' WITH 2 SX CMT ON TOP WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1178' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4474	4480		SPF
4436	4450		SPF
2902	2908		
2784	2796		SPF
2288	2294		
2236	2240		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

APR - 5 2013

KCC DODGE CITY

Signed

Richard M. Lacey
4/16/13

(TECHNICIAN)