

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23201-00-00  
Spot: SWNESESE Sec/Twnshp/Rge: 13-14S-18W  
667 feet from S Section Line, 450 feet from E Section Line  
Lease Name: JULIA HERL Well #: 2  
County: ELLIS Total Vertical Depth: 3556 feet

Operator License No.: 34347  
Op Name: BENCHMARK ENERGY LLC  
Address: PO BOX 8747  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3664		500 SX
SURF	8.625	1163		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2013 12:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JERRY NASH Company: PROFESSIONAL PULLING SERVIC Phone: (620) 672-1114

Proposed Plugging Method: Ordered 650 sx 60/40 pozmix 4% gel cement w/1200 # hulls and 7 sx gel.  
Shot perforations at 1700', 1175' and 550'.  
CIBP at 3200'.  
Perforations at 3488' to 3495'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2013 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3200' and pumped 7 sx gel followed by 50 sx cement w/200 # hulls.  
Pulled tubing to 1716' and pumped 300 sx cement w/400 # hulls. Lost circulation several times. Finally got circulation and ran out of cement. Pulled tubing out. Shut down for the evening.  
Ran tubing in and tagged cement at 1659. Pumped 300 sx cement w/600 # hulls. Got circulation out back side and casing is full.


Perfs:

Remarks: SOS TICKET # 680 AND 681

Plugged through: TBG

District: 04

Signed

  
4/16/13 (TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 05 2013

CONSERVATION DIVISION  
WICHITA, KS

MAR 25 2013