

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-22209-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 19-21S-33W  
475 feet from S Section Line, 1840 feet from W Section Line  
Lease Name: DORIS GREEN Well #: 5  
County: FINNEY Total Vertical Depth: 4800 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	336		WITH 225 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2013 8:30 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: STEVE CRAIG Company: H2 DRILLING LLC Phone: (620) 636-2090

Proposed Plugging Method: 1ST PLUG AT 2050' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 04/05/2013 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 2050' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED

Plugged through: DP

District: 01

Signed

*Richard M. Lacey*  
4/25/13

(TECHNICIAN)

RECEIVED

APR 16 2013

KCC DODGE CITY

Form CP-2/3

*ROCK*