

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20581-00-00
Spot: N2SENE Sec/Twnshp/Rge: 32-17S-10W
1650 feet from N Section Line, 660 feet from E Section Line
Lease Name: STEINERT A Well #: 1
County: ELLSWORTH Total Vertical Depth: 3244 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3150		
PROD	5.5	3241		100 SX
SURF	8.625	246		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2013 10:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GARY KIRMER Company: JOHN ROY EVANS Phone: (620) 793-2026

Proposed Plugging Method: SEE BELOW. CONDITION OF WELL -- POOR. GARY KIRMER THINKS THERE IS POSSIBLE CASING LEAK AROUND 1950'. WELL HAS BEEN SQUEEZED.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2013 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 3150' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1300', 950', AND 300'. RUN TUBING TO 1936' AND PUMP 25 SX'S CEMENT WITH 2% CC. PULL TUBING TO 1300' AND PUMP 35 SX'S WITH 2% CC. PULL TUBING TO 950' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 215 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3241	3244	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
APR 23 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. PIONEER WIRELINE TICKET #41278. COPELAND C-38455.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)
4/26/13