

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20212-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 32-19S-35W
2055 feet from S Section Line, 820 feet from W Section Line
Lease Name: VANCE Well #: 1-32
County: WICHITA Total Vertical Depth: 5250 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 352 | | WITH 250 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/03/2013 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: JIMMY SCHULTZ Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2340' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 04/03/2013 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2340' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Eric MacLaren
4/25/13
(TECHNICIAN)

RECEIVED

APR 12 2013

KCC DODGE CITY

Form CP-2/3

Handwritten initials