

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-30016-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 36-31S-4E  
2337 feet from S Section Line, 3642 feet from E Section Line  
Lease Name: HOLT Well #: 2  
County: COWLEY Total Vertical Depth: 2404 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	0	0		0 SX
PROD	5.5	2404		100 SX
SURF	8.625	177		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2013 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS / 25 SXS ON BOTTOM, 250'-0' CIRC. CMT.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/28/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2310', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. 3-25-2013, SHOT SQUEEZE HOLES @ 250'-251'. 3-26-2013, RIH W/TBG @ 255', COPELAND ACID MIXED & PUMPED 47 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TBG, SWEDGED INTO 5-1/2" CSG & PUMPED 58 SXS 60/40 POZMIX 4% GEL (105 SXS TOTAL). WELL ON VACUME. SDON. 3-27-2013, TAGGED CEMENT @ 1600'. 3-28-2013, RIH W/TBG @ 260', COPELAND ACID LAODED HOLE W/8 BBL FLUID, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #41827 & 41832.

Perfs:

Top	Bot	Thru	Comments
2368	2372		CSG

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 17 2013**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)  
4/25/13

124