

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20451-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 1-23S-2W
4823 feet from S Section Line, 5065 feet from E Section Line
Lease Name: SCHAUF Well #: 1
County: HARVEY Total Vertical Depth: 3024 feet

Operator License No.: 33526
Op Name: STUCKY, KENNETH R. OIL & GAS OPR.
Address: PO BOX 576
BURRTON, KS 67020

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3024	1700	100 SXS CMT
SURF	8.625	207		150 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2013 8:00 AM
Plug Co. License No.: 33948 Plug Co. Name: C & J PRODUCTION LLC
Proposal Rcvd. from: JAKE SIGEL Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC REQUIREMENTS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 04/09/2013 1:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2918 CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1700' PULLED CASING. RAN TUBING TO 409' PUMPED 35 SX OF GEL, THEN SPOTTED 35 SX OF COMMON CEMENT. PULLED TUBING TO 250' PUMPED 2 SX GEL, CIRCULATED TO SURFACE WITH 150 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
2974	2977		

RECEIVED
KANSAS CORPORATION COMMISSION
APR 23 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, COMMON CEMENT - TICKET #38423, WELL PLUG ON COMMISSION ORDER.

Plugged through: TBG

District: 02

Signed B. J. Hope
4/23/13 (TECHNICIAN)

JK