

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20653-00-00
Spot: SESWNW Sec/Twnshp/Rge: 3-23S-3W
3230 feet from S Section Line, 4200 feet from E Section Line
Lease Name: SCHRAG J Well #: 1
County: HARVEY Total Vertical Depth: 3402 feet

Operator License No.: 33526
Op Name: STUCKY, KENNETH R. OIL & GAS OPR.
Address: PO BOX 576
BURRTON, KS 67020

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3300		
PROD	4.5	3402	1700	125 SXS CMT
SURF	8.625	250		200 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/03/2013 12:00 PM
Plug Co. License No.: _____ Plug Co. Name: _____
Proposal Rcvd. from: _____ Company: WORX LLC #33948 Phone: (620) 382-4084

Proposed Plugging Method: AS PER KCC REQUIREMENTS.-- PLUGGING CONTRACTOR WORX LLC LIC #33948

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 04/03/2013 2:30 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SANDED OFF @ 3170' WITH 4 SX CAP. CUT CASING @ 1700' PULLED ALL THE CASING OUT, RAN BACK WITH TUBING TO 500' SET A 35 SX HOT PLUG OF CLASS A COMMON 3% C.C. LET IT SIT FOR ONE HOUR RAN SAND LINE TAGGED PLUG @ 400', PULLED TUBING UP TO 300' RAN 5 SX OF GEL THEN PUMPED 80 SX OF CLASS A COMMON WITH 3% C.C. PULLED ALL THE TUBING OUT OF THE HOLE. TOPPED OF THE SURFACE CASING WITH 10 SX. CHECKED PLUG 4/4 13 STAYED AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3272	3282		


RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: CEMENT TICKET #38415 COPLAND GREAT BEND -- PLUGGED DUE TO COMMISSION ORDER

Plugged through: TBG

District: 02

Signed


4/25/13 (TECHNICIAN)