

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20280-00-01  
Spot: NWSESW Sec/Twnshp/Rge: 22-15S-8W  
1052 feet from S Section Line, 3663 feet from E Section Line  
Lease Name: NEINKE Well #: 1  
County: ELLSWORTH Total Vertical Depth: 2350 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2273	1205	175 SX
SURF	8.625	279		175 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2013 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/22/2013 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2110' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 1205' AND PULL TO 900' AND PUMP 35 SX'S CEMENT, PULL CASING TO 650' AND PUMP 35 SX'S CEMENT, PULL CASING TO 330' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2169	2181	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 02 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-38510. THIS WELL WAS PLUGGED DUE TO WELL INVENTORY REVIEW BY CENTRAL OFFICE.

Plugged through: CSG

District: 02

Signed

*Virgil Clothier*  
5/16/13  
(TECHNICIAN)