

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20216-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 26-19S-36W  
427 feet from S Section Line, 412 feet from W Section Line  
Lease Name: SHIMANEK Well #: 1  
County: WICHITA Total Vertical Depth: 5355 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	266		WITH 200 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2013 5:30 PM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: CARLOS FIBELA Company: H2 DRILLING LLC Phone: (620) 636-2090

Proposed Plugging Method: 1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 04/10/2013 7:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 26 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

APR 23 2013

KCC DODGE CITY

Signed

*Michael Maier*  
5/10/13

(TECHNICIAN)

Form CP-2/3

*BMB*