

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20194-00-02
Spot: SENESW Sec/Twnshp/Rge: 4-27S-12W
1675 feet from S Section Line, 3002 feet from E Section Line
Lease Name: STUDER Well #: 1
County: PRATT Total Vertical Depth: 4455 feet

Operator License No.: 9582
Op Name: STUDER OIL CO.
Address: PO BOX 925
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4250	2450	WITH 250 SX CMT
SURF	8.625	325		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2013 2:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT ON BOTTOM. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2013 9:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 250# HULLS & 30 SX CMT. DISPLACED TO 3500'. 1ST PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 365' WITH 50 SX CMT. NEVER REGAINED CIRCULATION. SDON. 4/5/13: RUN IN & TAG CMT AT 780'. RUN CASING IN TO 365' TO RE-SPOT 2ND PLUG. 2ND PLUG AT 365' WITH 100# IN 7 SX GEL. HOLE CIRCULATED. SPOT 50 SX CMT W/3% CC. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4150	4192		
3877	3881		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

APR 12 2013

KCC DODGE CITY

Signed

Stephen J. Pfeifer
4/12/13 (TECHNICIAN)

Form CP-2/3

0107