

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25285-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 18-11S-18W
1400 feet from S Section Line, 2210 feet from E Section Line
Lease Name: FRISBIE M Well #: D1-18
County: ELLIS Total Vertical Depth: 3480 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
MSCC		1240		
PROD	5.5	3476		175 SX
SURF	8.625	213		160 SX
T1	2.875	3394		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2013 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement; 13 sx gel; 500 # hulls.
PC @ 1240 w/100 sx cement
PBTD=3440'
Well was squeezed
GPS: 39.09220 -099.35934
1374' FSL 2171' FEL SE SW NW SE

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2013 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Klima Well Service ran in hole with tubing to 3300' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls mixed in.
Pulled tubing to 1650' and pumped 150 sx cement w/300 # hulls mixed in to circulate cement to pit. Pulled tubing. Topped off 5 1/2" casing with 25 sx cement. Hole standing full.
Pulled bull plug out of 8 5/8" casing. Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3378	3380		
3251	3257		
3243	3246		
3236	3238		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 24 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING CO TICKET # 6655

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CA

APR 19 2013