

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21624-00-00  
Spot: E2W2NWSW Sec/Twnshp/Rge: 3-29S-8W  
1980 feet from S Section Line, 4695 feet from E Section Line  
Lease Name: NELSON A Well #: 1  
County: KINGMAN Total Vertical Depth: 4302 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: PO BOX 1278  
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4302		0 SX
SURF	8.625	260		170 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2012 12:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP 4075' & 2 SKS CEMENT, 35 SX 1200', 35 SX 800', CIRC 310' PBTD 4245.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/15/2012 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4075' & CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS PERFORATED AT 1200', 800' & 310'. TUBING WAS RUN TO 1200' WHERE 35 SKS OF CEMENT WAS SPOTTED. PULLED TUBING TO 795' & SPOTTED 35 SX CEMENT. SDFN. RAN WIRELINE & TAGGED CEMENT AT 700'. RAN TUBING TO 294' & CIRCULATED CEMENT TO SURFACE. WITH 150 SK CLASS A CEMENT.

Perfs:

Top	Bot	Thru	Comments
4137	4143	CSG	

Remarks: ALLIED CEMENT- CLASS A CEMENT.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*[Handwritten Signature]*  
9/17/13  
(TECHNICIAN)

RECEIVED

MAR 01 2013

Form CP-2/3

KCC WICHITA

*[Handwritten Initials]*