

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21203-00-01
Spot: SWNESW Sec/Twnshp/Rge: 28-10S-19W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: KELLER Well #: 1-28
County: ROOKS Total Vertical Depth: 3865 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3710		150 SX
SURF	8.625	187		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2013 1:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2013 1:30 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Perforated at 900', 1550' and 2050'.
Ran tubing to 3500'. Swift Cement Co pumped 100 sx cement w/300 # hulls. Pulled tubing to 2100' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 50 sx cement w/100 # hulls. Circulated cement. Pulled tubing out of hole and topped off with 10 sx cement. Back side full of cement.

GPS: 39.15175 -99.45041

Perfs:

Top	Bot	Thru	Comments
3594	3597		
3248	3250		
2731	2733		

Remarks: SWIFT CEMENT CO. TICKET # 23020

Plugged through: TBG

District: 04

Signed

Tom Culley
3/13/13 (TECHNICIAN) CM

FEB 11 2013

RECEIVED

FEB 19 2013

Form CP-2/3

KCC WICHITA