

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-01067-00-01
Spot: N2NESE Sec/Twnshp/Rge: 3-22S-19E
2310 feet from S Section Line, 660 feet from E Section Line
Lease Name: UNIT 3 Well #: W 8
County: ANDERSON Total Vertical Depth: 835 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	770		25 SX
SURF	7	0		0 SX

Well Type: EOR UIC Docket No: E05363.1 Date/Time to Plug: 01/24/2013 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out and top well off with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 01/24/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD AND FILL WITH CEMENT TO SURFACE. HOOK ON TO 2-INCH AND SQUEEZE. SHUT IN PRESSURE AT 1200 POUNDS. A TOTAL OF 25 SACKS WAS USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
811	827		

RECEIVED
MAR 13 2013
KCC Chanute Dist. #3
LS

Remarks:

Plugged through: TBG

RECEIVED
MAR 15 2013
KCC WICHITA

District: 03

Signed [Signature] 3/13/13
(TECHNICIAN)

* cc to UIC 3/20/13