

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23072-00-00  
Spot: NESESWNE Sec/Twnshp/Rge: 6-31S-14W  
3251 feet from S Section Line, 1596 feet from E Section Line  
Lease Name: BIBB Well #: 1-6  
County: BARBER Total Vertical Depth: 4685 feet

Operator License No.: 34110  
Op Name: CAERUS KANSAS LLC  
Address: 600 17TH ST, STE 1600 N  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	45		8 SX
PROD	5.5	3970	2840	WITH 175 SX CMT
SURF	8.625	1108		WITH 430 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2013 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BRIAN KARLIN Company: CAERUS KANSAS, LLC Phone: (785) 623-3290

Proposed Plugging Method: SAND TO 50' ABOVE PERFS WITH 5 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE  
Date/Time Plugging Completed: 03/20/2013 11:30 AM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SANDED TO 3000' WITH 5 SX CMT. 1ST PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3845	3849		
3110	3113		
3050	3053		

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 27 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Daniel Bernasconi  
4/10/13 (TECHNICIAN)

RECEIVED

MAR 22 2013

KCC DODGE CITY