

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26397-00-00
Spot: NWNESESE Sec/Twnshp/Rge: 24-14S-18W
1270 feet from S Section Line, 480 feet from E Section Line
Lease Name: STECKLEIN Well #: 1-24
County: ELLIS Total Vertical Depth: 3650 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	935		475 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/04/2013 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 02/04/2013 4:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3515 w/50 sx
2nd plug @1175 w/25 sx
3rd plug @950 w/40 sx
4th plug @450 w/80 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
MAR 04 2013
KCC WICHITA

District: 04

Signed CASE MORRIS
3/13/13 (TECHNICIAN)

FEB 18 2013